## **CHECKLIST**



## Sauna technology for sauna operators

When the stones have settled, remove them completely. Clean the rock store and clear it of brittle stones with deposits, stone fragments and residues. Replace with correctly sized stones suitable for the heater. Loosely stack stones again to achieve sufficient air flow.
ACCESSORIES  Do all attached parts such as brackets, heater guard rail, stack frames, sand timers, hygrometers, thermometers, etc. fit?
<b>DISTANCES</b> to flammable parts.  Is the heater still in the correct location? Were flammable parts retrofitted near the heater?  See safety distances in the respective operating instructions.
SUPPLY AIR & EXHAUST AIR OPENING as well as ventilation grille check. Sind die Öffnungen korrekt bzw. nicht verschlossen, verstopft, zugestellt? Evtl. vorhandene Lüftungsgitter von Fusseln und anderen Rückständen reinigen.
FUNCTION of all sauna components correct. e.g. does the switch work correctly? Are there visually detectable damages to the sauna components? e.g. to the lighting, heater, control unit, cables, etc.
SAFETY DEVICES if available, check for function and stability.
BASE AREA OF THE SAUNA HEATER clean and check for sauna stone particles or other residues.
CLEANING of painted and unpainted metal parts.  According to material and surface refinement at regular intervals, as well as all other sauna components, with suitable cleaning agents.
VAPORIZER TANK regularly decalcify and clean combination heaters. Reinigung / Entkalkung nur mit dafür geeigneten Mitteln. Erkundigen Sie sich auch nach Ihrer örtlichen Wasserhärte.

## ATTENTION! Please have your sauna system serviced regularly by a licensed specialist.